



8353 Demetre Ave.  
 Sacramento, CA 95828  
 (916) 381-5588 / (800) 400-1934  
 FAX: (916) 381-5522  
 CA Contractors Lic# 287715, SBE Vendor # 24508

Proposal

Proposal Id: 51475

Date: 4/30/2018

To:

Project:

MOUNT DIABLO SCHOOL DISTRICT  
 Attn: CHRISTIAN LEPE  
 1490 GASOLINE ALLEY  
 CONCORD, CA 94520  
 Email: lepec@mdusd.org

INSTALL (NJPA PROVIDED SPO18) LIFT  
 PROVIDE AIR AND ELECTRICAL  
 PIPE AIR ELECTRICAL AND HYDRAULIC LINES  
 DEMOLITION OF HALF WALL,

Sales Person: Jon Bonawitz Cell: 916-257-0708 Email: jbonawitz@airandlube.com

Description	Quantity	UOM	Unit Price	Extended Price
<b>A.01 Automotive Lifts 2200</b>				
Remove and dispose (1) 12k 2 post above ground lift. Install (1) NJPA provided Rotary SPO18 lift with air and electrical. Mount Diablo School District NJPA Member # 11092.				
ROTARY 2-POST 18K SYM (NJPA)	1.00	EA	16,451.37	16,451.37
LABOR-REMOVE AND DISPOSE (1) 12K 2PAG LIFT				580.00
LABOR- INSTALL (1) ROTARY SPO18 LIFT WITH AIR AND ELECTRICAL				3,110.25
MATERIAL- AIR, ELECTRICAL, FITTINGS, ETC.				330.05
SALES TAX-AUTOMOTIVE LIFTS	8.75	%	167.81	1,468.37
			<b>Sub Total</b>	<b>21,940.04</b>
<b>A.07 Reels and Piping 4400</b>				
Provide and install a vertical steel bracket to support the inground control pedestal and piping. Run (70') of 2" galvanized hydraulic feed line to lift controls. Run (70') of 1 1/2" galvanized hydraulic return line to lift controls. Run approx. (100') of 1" type L copper pipe to provide air at the control pedestal. Run approx. (70') of 3/4 EMT and provide a 110V electrical outlet. near the pedestal.				
LABOR- RE-ROUTE HYDRAULIC GALVINZED PIPING				5,075.00
LABOR- RUN (100') OF TYPE L 1" COPPER AIR LINE TO SPO18 LIFT & CONTROL PEDESTAL				2,071.43
LABOR- PROVIDE A 110 ELECTRICAL OUTLET AT LIFT PEDESTAL				580.00
LABOR- PROVIDE AND INSTALL A VERTICAL STEEL SUPPORT BRACKET				580.00
MATERIAL- GALVANIZED 1 1/2"-2" PIPING, FITTINGS, ETC				2,352.00
MATERIAL- 1" TYPE L COPPER AIRLINE (100') TO LIFT CONTROLS AND SPO18 LIFT				1,139.60
MATERIAL- 110V ELECTRICAL OUTLET AT INGROUND LIFT CONTROL				393.40
MATERIAL- VERTICAL STEEL PEDESTAL & PIPE SUPPORT BRACKET				359.80
SALES TAX-REELS & PIPING	8.75	%		371.42
			<b>Sub Total</b>	<b>12,922.65</b>



8353 Demetre Ave.  
 Sacramento, CA 95828  
 (916) 381-5588 / (800) 400-1934  
 FAX: (916) 381-5522  
 CA Contractors Lic# 287715 , SBE Vendor # 24508

**Proposal**

**Proposal Id: 51475**

**Date: 4/30/2018**

**To:**

MOUNT DIABLO SCHOOL DISTRICT  
 Attn: CHRISTIAN LEPE  
 1490 GASOLINE ALLEY  
 CONCORD, CA 94520  
 Email: lepec@mdusd.org

**Project:**

INSTALL (NJPA PROVIDED SPO18) LIFT  
 PROVIDE AIR AND ELECTRICAL  
 PIPE AIR ELECTRICAL AND HYDRAULIC LINES  
 DEMOLITION OF HALF WALL,

**A.28 Demolition 5300**

LABOR- DEMOLITION OF AN EXISTING HALF WALL		6,960.00
MATERIAL- REMOVE AND DISPOSE DEMO MATERIAL		252.00
SALES TAX-DEMOLITION	8.75 %	22.05
	<b>Sub Total</b>	<b>7,234.05</b>

**A.32 Equipment 9200**

FORKLIFT/SCISSORLIFT		1,206.00
	<b>Sub Total</b>	<b>1,206.00</b>

**Proposal Total: 43,302.74**

JB 4.48/1121

**TERMS AND CONDITIONS**

**\*\*Quote valid for 30 days.**  
**\*\*Quote does not include permits, permit fees or processing; engineering, or any other special requirements that may be set forth by Fed., State, County or City agencies.**  
**\*\*Terms: NET 5 unless otherwise arranged.\*\*Additional charges apply for: Thin floor requiring slab thickening, epoxy anchors, uneven floor requiring dry packing and any underground piping, conduit or utilities relocation. Lifts will not be installed on insufficient concrete per the manufacturers recommendation. Additional thickness may be required per local building code. Not included.**

Name

Date