

## BluSky Project Proposal – Westwood Elementary School

**Date:** 02/20/2024

**Client Name:** Mt. Diablo Unified School District

**Job #:** 1070248988

**POC:** Paul Lundholm

**Address:** 1748 West Street, Concord

### **Scope of Work – Asphalt**

1. Mobilization of crew and equipment
2. Remove existing asphalt approximately 4,300 sq ft
3. Haul off all spoils to local landfill
4. Install class II base rock if needed
5. Prep, grade, and compact subbase
6. Install 3" of new hot 1/2" asphalt via Leeboy paving machine
7. Compact solid using dual drum vibratory roller and wacker plates
8. Re-stripe lines per existing layout
9. Clean job site

### **Notes:**

- All work performed will be done with properly trained personnel in accordance with all EPA, AHERA, Cal/OSHA, DOT, and all other Local, State and Federal Regulatory Agencies.

\*Includes all hazardous waste hauling, disposal fees.

- Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate.

- Damage to pavement resulting from earth movement or abusive use shall not be considered contractors liability.

- NOT RESPONSIBLE FOR ANY CRACKING DUE TO DIVERSE SOIL CONDITIONS. NOT RESPONSIBLE FOR ANY DAMAGE TO WATER PIPES, ELECTRICAL CONDUIT OR GATE LOOPS UNDER SUB BASE OR ASPHALT.

### **Exclusions:**

1. Content Manipulation (unless otherwise specified in above scope of work)

**Price: \$56,007.48**

This proposal accounts for only the items listed under the scope of work, any additional services outside of the scope is subject to a change order & additional charge. All work will be conducted following all local, state, and federal guidelines. This estimate does not account for code or plan related repairs. This estimate is valid for 24 hours, after 24 hours, BluSky has the right to accept, reject or revise our proposal.

